

BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B**Desilting of drain and Removing and resetting Drains in ward No.05 surrounding area
Byatarayanapura**

SNo	Quantity	Item Name	Unit	Approved Rates of GOPIREDDY	
				In figures	In words
1	2387.28	Removing & Refixing stone slabs of drains and pointing in C.M (1:3) (Page No 27., I.No.5.33 of KPWD S.R 2018-19).	Sqm	116.81	Rupees One Hundred Sixteen And Paise Eighty One Only
2	1252.80	Earthwork in excavation for foundation of structure like culverts, retaining wall etc., as per drawing and technical specification, including setting out, construction of shoring and bracing, dressing of sides and bottom, back filling with approved material, disposal of balance earth as per specification, including cost of labour, HOM etc., complete. In all kinds of soil by manual means. (P.No.256, I.No.34.15.1 of PW,P&IWTD S.R 2018-19)	Cum	273.50	Rupees Two Hundred Seventy Three And Paise Fifty Only
3	1618.20	Providing granite slabs of selected quality roughly dressed having a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing etc., complete. I.No.5.31.1, Page no 27	Sqm	778.73	Rupees Seven Hundred Seventy Eight And Paise Seventy Three Only
4	33.35	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No-13,I No-4.6)	Cum	6031.81	Rupees Six Thousand Thirty One And Paise Eighty One Only
5	232.00	KSRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not less than 1800 kg/m ³ and having a minimum average compressive strength 4.00 N/mm ² confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 I.No.5.26.1, Page no 27	Sqm	1070.20	Rupees One Thousand Seventy And Paise Twenty Only
6	375.84	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete, 10 cms thick. Page No. 27/ Item No. 5.31.2 PWD SR 2018-19	Sqm	1014.57	Rupees One Thousand Fourteen And Paise Fifty Seven Only
7	375.84	Providing One line dressing to granite stone slab/ granite stone masonry as per speciication (P.No.26, I.No.5.17 of PW,P&IWTD SR 2018-19)	Sqm	997.89	Rupees Nine Hundred Ninety Seven And Paise Eighty Nine Only
8	651.24	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	2452.68	Rupees Two Thousand Four Hundred Fifty Two And Paise Sixty Eight Only
9		GST @ 12%			

G. of. f. d. s. g.
Contractor

H. V. 1
Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92